



Advisory

October 18, 2016

Subject:

Temporary gas connections on residential meter sets

Background:

In the past, ATCO has provided a lockable luboseal valve and quick connection downstream of the meter, to facilitate the use of temporary construction heat and unlocking permanent house gas lines upon completion of an acceptable gas inspection.

Advisory:

As of October 1, 2016, ATCO is no longer installing a lockable luboseal valve and temporary gas quick connection downstream of the meter. Builders and installers intending to use a gas hose and construction heaters connected to gas piping at the gas meter are now responsible for supplying their own quick connection.

With the removal of the lockable luboseal valve, it is the installer's responsibility to ensure the piping or tubing system is gas-tight and to perform pressure tests in accordance with CSAB149.1-15 Clause 6.22.2.

Note:

For further information on temporary construction heat please refer to The City of Calgary's [temporary construction heat advisory](#).